Ezzogenics Pte. Ltd.

59 Ubi Avenue 1 #06-16 Bizlink Centre Singapore S408938 +65 69683098 admin@ezzogenics.com www.ezzogenics.com Company Registration No.

Quotation QE0722PLF01



ADDRESS

201208665Z

50 Playfair Rd, #01-02 Singapore 367995

DATE 05/07/2022

TOTAL SGD 12,500.00

PROJECT

50 Playfair Rd

ACTIVITY	QTY	RATE	AMOUNT
Electrical works Location: 50 Playfair Rd, #01-02 Singapore 367995	1	0.00	0.00
(A) To fabricate & supply 1 unit 250A MSB -1x200A TPN MCCB 25k A/C w shunt trip	1	4,500.00	4,500.00

- 1x 200A TPN MCCB 25k A/C w shunt trip
- 2x63A TPN MCB 10kA TB
- 3x40A TPN MCB 10kA TB
- 4x20A TPN MCB 10kA TB
- 1x6A MCB 10kA TC
- 3x250/5A Metering CTs
- 1x63A 4P 100mA RCCB
- -2XELR c/w ZCT
- -1X Volt/Amp meter c/w selector switch
- -6x Indicator lights c/w fuse
- -1x Busbar support
- -1x lot bolt & nuts
- -1x Panel board c/w powder coating
- -1x Panel internal wiring
- 1 busbar
- -1x N&E link
- -1x PI/SI testing
- -1x SP terminal block
- -3x 250A HRC fuses

(2) 200A sub-man cable

Important note: This list is NOT complete and not exhaustive. There would be another quote for supply and installation of MCBs to cater to the various car grooming centre's machines such as the air-pump, waste water recycling, air-con, lighting, power outlets, etc. Some are already catered to in this MSB design.

a) To supply and install 1x Add 250A MCCB with enclosure board & install near the

entrance of unit #01-02

900.00 1

900.00

ACTIVITY		QTY	RATE	AMOUNT
(2b) To supply & run 1x set 250A sub-man cable from level 2 rise board with NEW trunking (Cable length estimate 6meters)	r room 500A	1	5,100.00	5,100.00
(2c) Supply and install 3x250A HRC fuse unit & short length 250A level 2 existing 500A BOARD FOR UNIT #01-21 Tap-off	A cable tap from	1	1,300.00	1,300.00
Test stock 3. Provide manpower technician for attendance for shutdown/turn	n-on	1	700.00	700.00
Payment terms: 1. Confirmation by way of e-sign and company chop with 50% de 2. Balance payment 50% upon completion of shutdown/turnon to the entrance of #01-02.				
(Note: Connection of cable from MCCB to in-unit's MSB is separa	ate)			
	ate)			

(2) If changes are made to the work scope by shifting, amending, correcting or re-doing any work (be it completed or already started) due to change of plan by the customer and through no fault of the contractor, additional charges shall be incurred.

(3) Job is confirmed with the invoice issued and deposit paid with quotation signed and stamped. Deposit paid is not refundable. Approved purchase order cannot be cancelled unless otherwise approved by the Contractor.

(4) Payment terms: As stated in the quote. We reserve the right to stop work if any payment due is not paid.

(5) Pay by cheque: "Ezzogenics Pte. Ltd" or

OCBC Bank: 555-846724001 or Paynow: 201208665Z

(8) The validity of quotation:14 days.

(9) Please sign and stamp on this quotation.

THANK YOU.

Accepted By Accepted Date