Ezzogenics Pte. Ltd.

59 Ubi Avenue 1 #06-16 Bizlink Centre Singapore S408938 +65 69683098 admin@ezzogenics.com www.ezzogenics.com



Quotation

ADDRESS QUOTATION QE1022POL2 DATE 06/10/2022

Parc Olympia MCST Plan No.4405 58 Flora Drive

#B1-65 Singapore 506867

ACTIVITY	QTY	RATE	AMOUNT
Hacking 1. Hacking, removal and disposal of existing parquet flooring. Floor area 9.6m x 18m.	1	2,000.0	2,000.00
Cement works 2. Supply and install cement screeding such that the internal floor finish level is higher than outside. Workscope: 1. Top up cement screeding up to 150mm 2. Construct up to 50mm side wall as physical barrier between curtain wall frame and base with internal cement screeding using Non Shrink Grout (Davco 180 or similar grade) 3. Application of Quicseal (Q104) or Davco (k11 Flexible Membrane) Waterproofing membrane	1,980	5.00	9,900.00
Parquet Supply & Install, Sanding & varnish Workscope to supply and install SPORTS VINYL 1.8m W x 20m L x 8mm T TO LAY IN ROWS with joint lines every 1.8m Measured area 9.6m (W) x 18m (L) = 172 sqm	1	28,500. 00	28,500.00
 Self-Leveling Compound 2-3mm @ \$2500 Supply and install Extreme Sport Vinyl Flooring for MFH Floor area 172sqm with wastage @ \$26000 			
Option: Workscope to supply and install new PVC Skirting to match with adjusted higher Floor Finish Level. For total length 190ft run @ \$4 /per ft run. Top up \$760 for the work			
Court Markings Supply materials (either Nippon Bodelac or Berger Court Paint) and expertise to repaint the badminton court to IBF standards.	1	550.00	550.00
Warranty: 1. Warranty provided is on the workmanship of the parquet works only for 1 Year. Warranty is not provided for water damage, wear and tear from usage. All parquet warranty does not include damage or defect or defacement from daily use, wear and tear or improper care of the user. There is NO warranty to waterproofing works arising from cement screening and waterproofing treatment completed at the base. Insufficient information is provided regarding as-build state and design of the existing curtain wall and missing weep holes to allow water flow out to the external environment.			
Payment terms:			

2. Balance payment 50% upon completion

1. Deposit 50% upon confirmation. Please e-sign on the quotation

TOTAL

- (1) All quoted works are quoted as-is only. Non-quoted items shall be subjected to additional charges.
- (2) If changes are made to the work scope by shifting, amending, correcting or re-doing any work (be it completed or already started) due to change of plan by the customer and through no fault of the contractor, additional charges shall be incurred.
- (3) Job is confirmed with the invoice issued and deposit paid with quotation signed and stamped. Deposit paid is not refundable. Approved purchase order cannot be cancelled unless otherwise approved by the Contractor.
 (4) Payment terms: 50% deposit upon confirmation of job, 50% balance upon completion with NO retention. We reserve the right to stop work if any payment due is not paid.
- (5) Pay by cheque: "Ezzogenics Pte. Ltd" or OCBC Bank: 555-846724001 or Paynow: 201208665Z
- (8) The validity of quotation:14 days.
- (9) Please sign and stamp on this quotation.

Accepted By

Accepted Date