

WEFIX SG PTE LTD
59 UBI AVENUE 1 #06-16
SINGAPORE
SINGAPORE 408938
67496032
DAVID@WEFIX.SG
Company Registration No.
201803163E

Quotation QW0121GLA02



ADDRESS

Yian Ching
#03-02 127 Lor K Telok Kurau,
Singapore 425766

DATE
31/01/2021

TOTAL
S\$2,000.00

PREPARED BY:
DC

DESCRIPTION	QTY	RATE	AMOUNT
Location: Suspected water leak from old piping at common toilet 1. Trouleshooting / repair / replacement and hacking out of surface wall plaster to replace leaking piping. - Includes patching back with waterproofing cement, plastering and paint for affected area only. Does not cover full wall. - Replacing with new copper piping (using stainless steel fittings connected by PZ1550 Hydraulic Crimping Tool). - Pressure test of replaced piping - Includes accessing and removing existing sink / u-drain pipe / tap fittings and fix back on completion of work - Painting of water damaged wall with white paint	1	1,600.00	1,600.00
2. Location: MBR Toilet Damaged copper piping above false ceiling to be replaced with new copper pipe / stainless steel fittings - Includes repairing false ceiling as required / painting of false ceiling - Additional epoxy putty for drain piping to ceiling slab. (Separate location from leaking piping) - Includes checking condition of concealed part of bath tub	1	550.00	550.00

Terms & Conditions :

- (1) All works are quoted as-is only. Non-quoted items shall be subjected to additional charges.
- (2) If changes are made to the work scope by shifting, amending, correcting or re-doing any work (be it completed or already started) due to change of plan by the customer and through no fault of the contractor, additional charges shall be incurred.
- (3) Job is confirmed with invoice issued and deposit paid or quotation sign/stamped. Deposit paid is not refundable. All work scope, method of delivery and conditions of the quotation are deemed accepted by customer once approval is given to start work or deposit paid or signed or stamped onto the quotation.

SUBTOTAL	2,150.00
DISCOUNT	-150.00

TOTAL	S\$2,000.00
-------	--------------------

THANK YOU.

(4) Payment terms: 50% Deposit with Balance 50% upon completion with NO retention. We reserve the right to stop work if progressive payment or any payment due is not paid.

(5) Pay by cheque:

"WEFIX SG Pte Ltd" or OCBC Bank: 712 619 790 001 or

Paynow: 201803163E

(8) Validity 14 days.

(9) Pls sign/stamp on this quotation

Accepted By

Accepted Date