Ezzogenics Pte. Ltd.

59 Ubi Avenue 1 #06-16

Bizlink Centre

Singapore S408938

+65 69683098

admin@ezzogenics.com

www.ezzogenics.com

GST Registration No.:

201208665Z

Company Registration No.

201208665Z

Quotation QE0123MSR1



ADDRESS

Matthew Lim

Lim Seng Kok Contractor Pte

Ltd

2 Namly Avenue

Singapore 267609

hp: 9848 1281

DATE 12/02/2023

TOTAL SGD 11,880.00

PROJECT

WPC @ 8 Meng Suan Road

ACTIVITY	QTY RATE	AMOUNT
WPC Flooring	1 11,000.00	11,000.00

Location: 8 Meng Suan Road Singapore 779211

Timber Bridge

1. Supply and install WPC composite timber decking plank with aluminium hollow section batten of size 50mm x 50mm x 3mm thk to timber decking; alum batten at 300mm c/c; 145mm (w) 2.4m

4mm gap between WPC composite timber plank using plastic click system 23mm

tnk X

length. Qty 30.86sqm

Note: Steel support system by main con

Timber Bridge

2. Supply and install WPC composite timber decking plank with aluminium hollow section of size 50mm x 25mm x 2mm thk sitting directly on steel hollow section @ 300mm c/c, 145mm (w) 2.4 m

including vertical fascia cladding to steel hollow sections; 4mm gap between WPC 23mm thk x

length composite timber plank using plastic click system. Qty 3.80sqm

Note: Steel support system by main con

ACTIVITY QTY RATE AMOUNT

Timber Staircase Step & Riser

3. Supply and install WPC composite timber decking plank with aluminium hollow section of size 50mm x 12mm thk alum batten at 350mm c/c sitting directly on steel chequer plate, including composite timber plank to vertical riser of steel staircase; 4mm gap between WPC composite timber plank using plastic click system 23mm thk x 145mm (w) x 2.4m length. Qty: 5sqm

Note: 5 thread and 6 risers

Note: Steel support system by main con

Note: Staircase dimensions - R - 250mm and T: 170mm

4. Timber Cladding

Supply and install WPC composite timber decking plank with aluminium hollow section

23mm thk x

batten of size 50mm x 12mm to timber cladding; alum batten at 350mm c/c, 4mm gap 145mm (w) x 2.4m between WPC composite timber plank using plastic click system; assume no top length capping; cladding height is 0.5m. Qty 10.95sqm

Quotation is quoted as 1 Lot

Payment terms:

- 1. Please e-sign on the quotation
- 2. Deposit 50% upon confirmation.
- 3. Balance payment 50% upon completion with no retention. Completion should be before project handover by Main Contractor to their customer.

Terms & Conditions :	
(1) All quoted works are quoted as-is only. Non-quoted ite	n

(1) All quoted works are quoted as-is only. Non-quoted items shall be subjected to additional charges.

- (2) If changes are made to the work scope by shifting, amending, correcting or re-doing any work (be it completed or already started) due to change of plan by the customer and through no fault of the contractor, additional charges shall be incurred.
- (3) Job is confirmed with the invoice issued and deposit paid with quotation signed and stamped. Deposit paid is not refundable. Approved purchase order cannot be cancelled unless otherwise approved by the Contractor.
- (4) Payment terms: As stated in the quote. We reserve the right to stop work if any payment due is not paid.
- (5) Pay by cheque: "Ezzogenics Pte. Ltd" or

OCBC Bank: 555-846724001 or Paynow: 201208665Z

- (8) The validity of quotation:14 days.
- (9) Please sign and stamp on this quotation.

 SUBTOTAL
 11,000.00

 GST TOTAL
 880.00

TOTAL SGD 11,880.00

THANK YOU.

Accepted By Accepted Date