Ezzogenics Pte. Ltd.

59 Ubi Avenue 1 #06-16

Bizlink Centre

Singapore S408938

+65 69683098

admin@ezzogenics.com

www.ezzogenics.com

Company Registration No.

201208665Z

Quotation QE0322TV2-01



**ADDRESS** 

THOMSON V TWO

MCST3918

Attn: William

11 SIN MING ROAD#01-13

THOMSON V TWO Singapore 575629

DATE 02/03/2022

TOTAL SGD 46,675.00

**PROJECT** 

TV2 - Toilet

ACTIVITY	QTY	RATE	AMOUNT
Hacking  1. Hacking work	1	6,000.00	6,000.00
<ul> <li>To dismantle all existing washing basin counter top (Male, Female &amp; handicap Toilet)</li> </ul>			
<ul> <li>To hack existing all toilet floor tiles (Male, Female &amp; handicap Toilet)</li> <li>Removal of false ceiling to be replaced</li> <li>Includes disposal of debris to MCST's own skip bin</li> </ul>			
Masonry 2. Supply labour & material to lay floor & wall tiles c/w waterproofing for all toilet floor tiles with sloped towards drainage or floor trap - Cost of tiles selected up to \$3psf (including GST)	1	15,000.00	15,000.00
Painting 3. Supply labour & material to paint ceiling using SS345 grade paint (for 3 toilets)	1	2,500.00	2,500.00
Countertop 4. Supply labour and material to fit new marble stone look Quartz washing basin counter top. ( 2260 mm L curved x 300mm H x 350mm D)	1	1,850.00	1,850.00
Carpentry  5. CARPENTRY WORKS - TOILET  - Design and fabricate cabinet below marble counter top c/w internal PVC and laminate finish. 3 storage spaces with 2 drawer dustbin. [2260mm L curved x 200mm H x 350mm D] @ \$1500  - Wood board / Laminated behind mirror at the washing basin ( Male & Female ) - @ \$1200 per toilet  - Wood board / Laminated above washing basin ( Male & Female ) - \$1500 per toilet	1	4,200.00	4,200.00

ACTIVITY	QTY	RATE	AMOUNT
Door 6. Door work - To dismantle existing male toilet entrance door and fit in new door. P	1 roposal for	1,950.00	1,950.00
size 10mm T x 2100mm H x up to 850mm W) Frosted Tempered Glas including stainless steel accessories - @ \$1200. (To use back existing - To dismantle existing steel and wood frame inside male toilet @ \$750mm = 100mm	s Door   frame)		
Electrical works	1	3,800.00	3,800.00
<ul> <li>7. Electrical works</li> <li>To supply labour and material to add new additional points for lighting</li> <li>Cove light behind mirror using LED SMD 5050 14.4W Strip lighting w</li> <li>driver @ \$800</li> </ul>			
- Supply and install 9 downlights for 3 toilets. To use back existing ligh New lighting points quoted at \$70 per point. @ \$500 - Approx. 20m LED SMD5050 strip light for both male and female toile			
power supply. Frosted cover for the lighting @ \$2500			
Plumbing	7	350.00	2,450.00
8. Plumbing To provide labour to remove and install washing basin (manual type) unew or old wash basin.	using either		
<ul> <li>Need to remove and install. Quote for manual type mixer only</li> <li>*If reusable, Supply labor to fit current washing basin to new marble of the current washing basin to new marb</li></ul>	counter top (		
Male, Female and Handicap toilet, 7 in total) • *If new Supply labor to fit new washing basin to new marble counter to Female and Handicap toilet, 7 in total)	top ( Male ,		
Provide a PUB Notification by a licensed plumber if needed (addition)	al \$500)		
False Ceiling	1	2,250.00	2,250.00
<ul> <li>9. Ceiling work:</li> <li>- Supply materials and install for False ceiling Above cubical area (Ma</li> <li>- Supply materials and install for False ceiling Above washing basin (r</li> <li>- Supply materials and install - Patching and changing of current light plead to changes in current ceiling</li> </ul>	male toilet )		
<b>Toilet Fixtures</b> 10. Supply and install toilet cubicles including disposal of old cubicles	7	725.00	5,075.00
Cleaning 11. Cleaning of Male / Female and Handicap toilets prior to handover voleaning.	1 with acid	1,600.00	1,600.00
Payment terms:  1. Deposit 40% upon confirmation. Please e-sign on the quotation  2. 1st claim: 50% upon completion of tiling work.  3. Balance payment 10% upon completion			
Terms & Conditions :			
(1) All quoted works are quoted as-is only. Non-quoted items			
shall be subjected to additional charges.	TOTAL SGD 46,675.00		
(2) If changes are made to the work scope by shifting, amending, correcting or re-doing any work (be it completed or			THANK YOU.
already started) due to change of plan by the customer and			THAINK 100.

through no fault of the contractor, additional charges shall be

(3) Job is confirmed with the invoice issued and deposit paid with quotation signed and stamped. Deposit paid is not refundable. Approved purchase order cannot be cancelled

incurred.

unless otherwise approved by the Contractor.

(4) Payment terms: As stated in the quote. We reserve the right

to stop work if any payment due is not paid.

(5) Pay by cheque: "Ezzogenics Pte. Ltd" or

OCBC Bank: 555-846724001 or Paynow: 201208665Z

- (8) The validity of quotation:14 days.
- (9) Please sign and stamp on this quotation.

Accepted By Accepted Date